



MIS

Date _____

REQUEST FOR PRICE QUOTATIONS
 No. C17-039-04

GENTLEMEN:

You are cordially invited to submit and quote your lowest price on the following supplies, materials and/or equipment listed hereunder. Please be informed that this procuring entity shall only consider price quotations within Approved Budget Cost (ABC) Php270,000.00

Your price quotation shall include the following documents and submitted in a sealed envelope, indicating the Solicitation No. / Reference No.:

- | | |
|--|--|
| 1. Proposal in your official letterhead; | 6. Latest Business Tax Return for the last two (2) quarter before the opening of the quotations; |
| 2. Copy of this request; | 7. Mayor's Permit; |
| 3. Brochure (if applicable); | 8. Tax Clearance; |
| 4. Philgeps Registration; | 9. Omnibus Sworn Statement |
| 5. Annual Income Tax Return; | |

Note: Item No. 4 to 8 not required if already submitted in previous CAAP projects as long as document is still valid.

Furthermore, the period of delivery must be within 15 calendar days from your receipt of the procuring entity's contract agreement and notice to proceed.

Submission of quotations must be made at this Office on or before the opening of quotations scheduled on April 26 2017 at 10:00 AM, at the CAAP-Procurement Division, Old QRT Building.

Please be guided accordingly.

Very truly yours,


PILARDITO D. BRIGOLA
 Chairman, Canvass and Contract Committee

| Qty | Unit | COMPLETE DESCRIPTION OF ARTICLE | Unit Price | Amount |
|-----|------|--|------------|--------|
| | | Purchase of materials for the renovation of proposed additional AANSOO office (former ICACS Office) (please see attached bill of materials) | | |

The Chairman, Canvass and Contract Committee
 Civil Aviation Authority of the Philippines
 Pasay City, Metro Manila

Sir:

In compliance with your request for price quotations and in behalf of _____
 We hereby commit to faithfully comply with all the requirements relative to this request. It is fully understood that our failure to furnish and deliver the items as herein quoted will disqualify our firm to participate in future biddings conducted by the Authority.

 (sign over printed name)

 (position)

NAME OF PROJECT : **PURCHASE OF MATERIALS FOR THE RENOVATION OF PROPOSED
ADDITIONAL AANSOO OFFICE (FORMER ICACS OFFICE)**

LOCATION : **G/F, CAAP Admin Bldgs. Old Mia Road, Pasay City**

SUBJECT : **BILL OF QUANTITIES**

| ITEM | DESCRIPTION | QTY | UNIT | UNIT PRICE | AMOUNT |
|-----------------------------|--|------|-------|------------|------------------|
| I. CEILING WORKS | | | | | |
| | 2' x 4' PVC Laminated Gypsum Boards (Orange Skin) | 103 | pcs. | 175.00 | 18,025.00 |
| | Wall angle 12' (ceiling grid) Bailey | 31 | pcs. | 150.00 | 4,650.00 |
| | Main Tee 12' (ceiling grid) Bailey | 26 | pcs. | 150.00 | 3,900.00 |
| | Cross Tee 4' (ceiling grid) Bailey | 84 | pcs. | 50.00 | 4,200.00 |
| | Cross Tee 2' (ceiling grid) Bailey | 87 | pcs. | 25.00 | 2,175.00 |
| | G.I. Tie Wire #16 | 2 | cls. | 100.00 | 200.00 |
| | Steel angle | 60 | pcs. | 10.00 | 600.00 |
| | 3/16" dia. X 1" Metal screw w/ toks | 100 | pcs. | 2.00 | 200.00 |
| | 3/16" dia. Concrete drill bit (heavy duty) | 2 | pcs. | 150.00 | 300.00 |
| | Concrete Nail 1-1/2" | 1 | kl. | 100.00 | 100.00 |
| | Concrete Nail 1" | 1 | kl. | 100.00 | 100.00 |
| | sub-total | | | | 34,450.00 |
| II. PARTITIONS | | | | | |
| | 4' X 8' X 6.0mm thk. Fiber Cement Board (Hardiflex) | 19 | pcs. | 750.00 | 14,250.00 |
| | 76mm x 3.0m(L) x 0.6mm thk. Metal studs | 16 | pcs. | 175.00 | 2,800.00 |
| | 76mm x 3.0m(L) x 0.5mm thk. Metal tracks | 17 | pcs. | 150.00 | 2,550.00 |
| | 1" x 4" x 12' S4S Lumber | 4 | pcs. | 300.00 | 1,200.00 |
| | Self drill Hardiflex screw 1" | 1000 | pcs. | 0.75 | 750.00 |
| | Self drill Hardiflex screw 2" | 50 | pcs. | 1.25 | 62.50 |
| | 400 pcs. - 1/8 dia. X 1/2" Blind rivets | 1 | box | 500.00 | 500.00 |
| | Diamond (Concrete) Cutter 4" dia. | 2 | pcs. | 500.00 | 1,000.00 |
| | 1/8" dia. Metal drill bit (heavy duty) | 5 | pcs. | 150.00 | 750.00 |
| | Screw bits, phillips #2 | 3 | pcs. | 35.00 | 105.00 |
| | sub-total | | | | 23,967.50 |
| III. FLOOR WORKS | | | | | |
| | Carpet Vinyl tiles 450mm x 450mm x 3.0mm thk. | 282 | pcs. | 175.00 | 49,350.00 |
| | Water based vynil adhesive (Odorless) | 6 | gals. | 650.00 | 3,900.00 |
| | Emulsion wax | 1 | gals. | 800.00 | 800.00 |
| | sub-total | | | | 54,050.00 |
| IV. ELECTRICAL WORKS | | | | | |
| | 600mm X 600mm Recessed mounted louver type lighting fixture, with mirrorized aluminum reflector and 2-9 watts (T-8) LED tube with 8,000 lumens and 20,000 hours lifetime (minimum) universal, 185V-265V, 60Hz. | 26 | sets | 2,500.00 | 65,000.00 |
| | 150mm dia. Recessed mounted vertical lamp downlight fixture with powder coat finish casing ad matte aluminum reflector w 1-8watts | 3 | sets | 700.00 | 2,100.00 |

230V, 60Hz LED pin light/bulb

| | | | | |
|--|-----|-------|----------|------------------|
| Single switch with plate and bracket, wide series | 1 | set | 130.00 | 130.00 |
| 2-gang switch with plate and bracket, wide series | 1 | set | 190.00 | 190.00 |
| 3-gang switch with plate and bracket, wide series | 1 | set | 240.00 | 240.00 |
| 150m - 3.5 sq.mm stranded THHN wire with thermoplastic insulator | 1 | box | 3,500.00 | 3,500.00 |
| 150m - 3.5 sq.mm stranded THHN wire with thermoplastic insulator | 1 | box | 2,800.00 | 2,800.00 |
| 1/2" dia. EMT connector | 100 | pcs. | 15.00 | 1,500.00 |
| 1/2" dia. Straight connector | 100 | pcs. | 16.00 | 1,600.00 |
| 1/2" dia. Flexible Hose metal | 30 | mtrs. | 50.00 | 1,500.00 |
| 3/8" dia. Mica Tube | 20 | mtrs. | 25.00 | 500.00 |
| G.I. Tie Wire #16 | 2 | cls. | 100.00 | 200.00 |
| sub-total | | | | 79,260.00 |

V. PAINTING WORKS

| | | | | |
|--|----|-------|----------|------------------|
| Flatwall latex paint, white (premium quality) | 7 | gals. | 550.00 | 3,850.00 |
| Flatwall enamel paint, white (premium quality) | 4 | gal. | 600.00 | 2,400.00 |
| Quick Dry Enamel paint, white (Premium quality) | 2 | gals. | 650.00 | 1,300.00 |
| Odorless antibacterial paint, soft ecru (Lead free) | 10 | gals. | 1,500.00 | 15,000.00 |
| Odorless antibacterial paint, chocolate kiss (Lead free) | 2 | gals. | 1,450.00 | 2,900.00 |
| Odorless paint, Tulle white (Lead free) | 2 | gals. | 1,450.00 | 2,900.00 |
| Paint thinner | 2 | gals. | 250.00 | 500.00 |
| Body filler (Polytuff) w/hardener | 2 | gals. | 650.00 | 1,300.00 |
| Extra Body filler hardener (big) | 2 | tube | 100.00 | 200.00 |
| Glazing Putty | 1 | gal. | 600.00 | 600.00 |
| Masonry Putty | 1 | gal. | 600.00 | 600.00 |
| Powdered Joint Compound | 20 | cls. | 35.00 | 700.00 |
| 4" Roller paint brush | 2 | pcs. | 65.00 | 130.00 |
| 7" Roller paint brush | 2 | pcs. | 95.00 | 190.00 |
| 2" Paint Brush | 2 | pcs. | 55.00 | 110.00 |
| 1" Paint Brush | 2 | pcs. | 35.00 | 70.00 |
| 6" Paint scrapper (heavy duty) | 4 | pcs. | 100.00 | 400.00 |
| Roller pan | 4 | pcs. | 75.00 | 300.00 |
| Fiberglass mesh tape 2" x 250' | 2 | rolls | 400.00 | 800.00 |
| Sanding paper #100 | 3 | mts. | 150.00 | 450.00 |
| Sanding paper #200 | 25 | pcs. | 15.00 | 375.00 |
| sub-total | | | | 35,075.00 |

VI. CARPENTRY WORKS

| | | | | |
|------------------------------------|----|------|----------|----------|
| 4' x 8' X 1/4" thk. Marine plywood | 5 | pcs. | 400.00 | 2,000.00 |
| 3/4" thick Marine plywood | 2 | pcs. | 1,400.00 | 2,800.00 |
| 2" x 2" x 12' Lumber rough | 18 | pcs. | 220.00 | 3,960.00 |
| 2" x 3" x 12' Lumber rough | 3 | pcs. | 330.00 | 990.00 |
| 1" x 2" x 12' wooden cornice. | 8 | pcs. | 200.00 | 1,600.00 |
| 1/2" x 2" x 12' Lumber (S4S) | 10 | pcs. | 120.00 | 1,200.00 |

| | | | | |
|---|--------------------------|------|----------|-------------------|
| Entrance lockset, lever type (heavy duty) | 3 | sets | 1,000.00 | 3,000.00 |
| Door closer (heavy duty) | 3 | sets | 3,500.00 | 10,500.00 |
| Concealed Hinges #1 | 10 | pcs. | 120.00 | 1,200.00 |
| Concealed Hinges #2 | 20 | pcs. | 120.00 | 2,400.00 |
| 1" Fin. Nail | 1 | kl. | 90.00 | 90.00 |
| 2" Fin Nail | 1 | kl. | 90.00 | 90.00 |
| 2" C.W. Nail | 2 | kls. | 90.00 | 180.00 |
| 3" C.W. Nail | 2 | kls. | 90.00 | 180.00 |
| 3" Concrete Nail | 1 | kl. | 120.00 | 120.00 |
| Wood Glue (Stikwell) | 1 | kl. | 150.00 | 150.00 |
| | sub-total | | | 30,460.00 |
| TOTAL COST | | | | 257,262.50 |

Prepared by :



MARIO T. MAGPOC
OIC, Facilities Maintenance Division



NAME OF PROJECT : **PURCHASE OF MATERIALS FOR THE RENOVATION OF PROPOSED
AANSOO EXTENSION OFFICE (FORMER ICACS OFFICE)**
LOCATION : **G/F, CAAP Admin Bldgs. Old Mia Road, Pasay City**
SUBJECT : **SCOPE OF WORKS**

I. CEILING WORKS

Replacement/Modification of existing wooden ceiling materials to PVC laminated boards provided with metal ceiling grids as specified on attached plans.

II. PARTITIONS

Provision of fiber cement board partition for the separation of ICACS Office as indicated plans.

III. FLOOR WORKS

Replacement/Modification of existing old carpet tiles to carpet vinyl tiles as indicated on plans.

IV. ELECTRICAL WORKS

Installation of proposed lighting fixtures, electrical lines to include accessories and electrical devices as indicated on plans

V. PAINTING WORKS

Painting /Repainting of interior portion of proposed AANSOO Office to include newly installed materials with the following finishes;

OFFICE

- | | |
|---|---|
| 1. Concrete walls and newly installed fiber cement boards | a. one coat of Flat latex paint (white) b. Two coats of odorless paint (color soft ecru) |
| 2. Wooden walls | a. one coat of Flatwall enamel paint (white) b. Two coats of odorless paint (color soft ecru) |

PANTRY AND TOILETS

- | | |
|-------------------|---|
| 1. Concrete walls | a. one coat of Flat latex paint (white) b. Two coats of odorless paint (color tulle white) |
| 2. Wooden walls | a. one coat of Flatwall enamel paint (white) b. Two coats of odorless paint (color tulle white) |
| 3. Wooden ceiling | a. Two coats of flatwall eamel paint (white) |


OTHERS

- | | |
|---|--|
| 1. Wooden door, door jambs and baseboards | a. one coat of Flatwall enamel paint (white) b. Two coats of odorless paint (color choco kiss) |
| 2. Wooden cabinets | a. Two coats of flatwall eamel paint, white (interior portion) b. Two coats of QDE paint (exterior portion) |

VI. CARPENTRY WORKS

1. Replacement of door lockset and provision of door closer at front, back and interior door.
2. Repair/Replacement of dilapidated wooden cabinet doors and concealed hinges.
3. Replacement of dilapidated wooden ceiling materials located at toilet, pantry and hallway pantry.

Prepared by:



MARIO T. MAGPOC

OIC Facility Maintenance Division