



September 27, 2017

REQUEST FOR PRICE QUOTATION

The Civil Aviation Authority of the Philippines (CAAP) Plaridel hereby invites interested bidders for the Purchase/Installation/Integration of Intercom System at San Jose Airport.

A. Approved budget – Php 299,989.52

(Please secure Canvass form at the Office of the Airport Manager Plaridel Airport during office hours Monday to Friday Starting September 28, 2017 onwards).

The sealed quotation shall be submitted at Plaridel Airport, Plaridel Bulacan on or before October 5, 2017 at 9:00 AM to the Bids and Awards Committee c/o the Office of the Airport Manager and will be opened on the same date at 10:00am. Indicate in the sealed envelope the name of Project you are participating.

The CAAP – Plaridel Airport reserves the right to accept or reject any bid, and to annul the bidding process and reject all Bids at any time prior to contract award without thereby incurring any liability to the affected Bidder/s.

You may call Riz Yaneza BAC Secretariat Plaridel Airport at (044) 794-7071 for details.

Very truly yours,

A handwritten signature in blue ink, appearing to read 'RPA', is written over a blue horizontal line.

ROLDAN P. ABEJUELA
Chairman BAC

Name of Project:		Purchase/Installation/Integration of Intercom System		
Location:		San Jose Airport		
QTY	UNIT	DESCRIPTION	UNIT COST	AMOUNT
		I. Cutting of existing concrete pavement		
1	lot	Cutting of existing concrete pavement Rental of Concrete Cutter		
			Sub Total	
		II. Excavation/Backfilling		
		200 x 0.3 x 0.5 = 30 cu.m		
1	lot	Excavation/Backfilling		
			Sub Total	
		III Sealing Concrete Pavement		
10	bags	Portland Cement		
5	cu. M	Gravel, # G4		
5	cu. m	Sand, # S1		
			Materials	
			Labor	
			Sub Total	
		IV. Installation/Integration of 14 Station Intercom System		
1	lot	Multi-Channel Selective Intercom Station 14 Station All Master Network Configuration complete with terminal blocks and 12V Power Supply		
500	mtrs	Minimum of 10 pairs intercom cable		
150	mtrs	1" dia. Electrical Flexible pipe		
2	pack	8" Plastic cable tie		
20	pcs	Self Adhesive PVC cable trunking 25 x 16 mm, 3m		
8	pcs	PVC cable trunking coupling 25 x 16mm		
5	pcs	PVC cable trunking elbow 25 x 16mm		
16	pcs	PVC cable trunking enclosure surface mount		
80	pcs	1 1/2" dia. PVC Rigid conduit		
12	pcs	1 1/2" dia. PVC Rigid long elbow		
14	pcs	1 1/2" dia. RSC pipe		
14	pcs	1 1/2" dia. RSC coupling		
80	pcs	Expansion bolt		
1	lot	RSC Brace, Bracket & clamp		
10	pcs	Metal pull box W150 X D150 x H150		
10	pcs	Metal pull box W200 x D200 x H200		
3	roll	Corrosive tape or Rubber tape		
			Materials	
			Labor	
			Sub Total	
GRAND TOTAL				

